



Betonqualität
quality of concrete
min.C20/25
normal bewehrt
normal armouring

* min. 160 mm wenn die Hebebühne
verdübelt werden soll
min. 160 mm if the lift should be fixed

Bauseits am Bedienpult bereitstellen:
Netzanschluss: 3 PH,N+PE,400V,50Hz
Motorleistung: 2,2 kW
Absicherung: 16 Ampere träge
Kabellänge: ca.2 m, 5x2,5 mm²

Eigengewicht ca. 405 kg
own weight
Tragfähigkeit: max.3000kg
capacity

Prepared by customer at the main operating unit:
power supply: 3 PH,N+PE,400V,50Hz
Motor power: 2,2 kW
fuse: 16 Ampere, time lag
cable diameter: 5 x 2,5 m² cable length: approx. 2m

Alle Maße in Millimeter
all dimensions in millimeter
Maß- und Konstruktionsänderungen vorbehalten!
subject to alterations!

				THIRD ANGLE PROJECTION	XS30 CAT	
				DO NOT SCALE DRAWING	Data sheet	
				UNLESS OTHERWISE SPECIFIED: 0.8mm MIN. CORNER BREAK REMOVE ALL BURRS		
NOTES:				UNLESS OTHERWISE NOTED: ANGULAR DIMENSIONS: +/- 1° OTHER DIMENSIONS: +/- 0.8mm (<305mm) +/- 1.6mm (>or= 305mm)		
REV	CO NUM	DATE	BY	The design and detail illustrated in this drawing is the property of Vehicle Service Group. It is being loaned with the expressed condition that it will not be duplicated or used except by permission and is subject to return upon request.		DRAWN MG
						DATE 28.12.2017
						SHEET DRAWING NUMBER
				APPROVED		Scissor-Lift_XS30CAT_8826